FOR QUARRY PROJECTS
ENVIRONMENTAL MANAGEMENT PLAN

POTENTIAL IMPACT PER PROJECT ACTIVITY PER PROJECT PHASE	MITIGATING MEASURES	RATING/ PERFORMANCE OF MITIGATING MEASURES						
A. Construction Phase	A. Construction Phase							
A.1 Site Development (Site Clearing, Removal of overburden, Road Network Development (ISAG), Construction of processing and other Related Facilities crushing/vobro/sand washing plant))								
Degradation of surface water quality due to contamination from domestic wastewater (with crushing / vibro/ sand washing plant)	 Provide portalets for the construction workers Note: at least one (1) portalet for 60 workers where the number of male workers exceeds 500 (as per IRR-Industrial Hygiene, PD 856 Amending Administrative Order 111 Series of 1991) 	100% complaint with RA 9275						
	Note: at least one (1) portalet for 25 workers where the number of male workers exceeds 100 (as per IRR-Industrial Hygiene, PD 856 Amending Administrative Order 111 Series of 1991)							
	 Hauling of sewage from portalets by third party service provider shall be covered by a licensed/permit from LGU and with valid Discharge Permit for the wastewater treatment facility 							
Potential siltation of nearby drainage system/ water bodies due to soil erosion (with crushing plant)	 Provision of silt traps/ponds for the surface run-off Provision of engineering and/or environmental measures to control the rate of erosion and siltation 							
Generation of dust from site preparation/removal of overburden	 Sprinkling of water along the access road and project area at least twice a day especially during dry season Vehicles transporting aggregates/construction materials should be adequately covered with tarpaulin canvass or jute sacks at all times 	100% compliance to RA 8749						

Generation of noise	II	100%
due to construction	• Use of mufflers, silencer, and exhaust pipes for construction	compliance to
and installation of	equipment	NPCC MC 02
equipment (for		Series of 1980
crushing/vibro/sand		
washing plant) Generation of spoils	• Excess spoils to be hauled for	100%
such as excess fill	proper disposal	compliant with
materials from	 Trucks tires should be thoroughly 	RA 9003
grading and	washed before leaving the project	
excavation activities	site (if applicable)	
and solidwaste	• Spoils shall be stockpiled on flat	
	areas and away from drainage	
	routes and nearby water bodyProvision of MRF and proper	
	segration of solidwaste, recyclables	
	will be sold to junkshop and	
	residuals will be disposed off to a	
	sanitary landfill.	1.0.00
Generation of used	Provision of storage for hazardous	100%
oil, BFL and other	wastes with proper labellingCollection and treatment of	compliance to RA 6969
hazardous materials	hazardous wastes by DENR	101 0505
(for crushing, vibro,	accredited 3rd party hauler and	
sand washing plant)	treater	
B. Operational Phase		
	elivery of raw materials and finished pro	oducts with with
crushing/vibro/sand Degradation of	Provision of multi-chambered	100%
surface water quality		complaint with
due to	• Siphoning/desludging septic tank	<i></i>
contamination from	by third party shall be conducted	
domestic wastewater	every 3 years from the start of	
	operation covered by a	
	licensed/permit from LGU and with valid Discharge Permit for the	
	wastewater treatment facility	
Potential siltation	Provision of temporary sand barrier	100%
(turbidity) during	from the active site/area of	
Extraction and	extraction (if applicable);	RA 9275
operation of	• Provision of silt curtain (if	
crushing/ bivro/ sand washing plant	applicable)	
Saira wasiiiig piaiit	• Implementation of the appropriate method of extraction as identified	
	by MGB	

	Provision of siltation ponds	
Potential accidents from landslides/falling debris Generation of dust and noise from heavy equipment and crusher/vibrating screens etc.	 Provision of measures such as to prevent/arrest falling debris and landslide to protect the public Provision of water sprinklers at the vibrating screen Water sprinkling of dirt roads, and provision of enclosures or muffling devices on engines and equipments Daytime operation only, or secure permit/clearance from concerned barangay if operating at nighttime 	100% no accidents from landslides/ falling debris 100% compliant to RA 8749
Generation of noise from delivery trucks / generator set Generation of noise from blasting operation (if applicable)	 Use of mufflers, silencer, and exhaust pipes as applicable Use of controlled blasting method 	100% Noise within standard (NPCC MC 002 Series of 1980)
Generation of solid wastes	 Provison of Materials Recovery Facility (MRF) Hauling of domestic wastes by third party contractor with permit/clearance from LGU for proper disposal of wastes . Composting of biodegradables onsite (if any) 	100% compliant to RA 9003
Generation of used oil (from motorpool) and other hazardous materials (ie. used batteries, fluorescent lamps) (with Crushing)	 Provision of storage facility/area and collection of hazardous wastes by DENR accredited 3rd party hauler and treater 	compliant to RA
Generation of effluents due to wastewater generation	 Monitoring of the following significant effluent quality parameters: ☑ BOD ☑ Total Suspended Solids 	100% compliance with DENR effluent standards (RA 9275); (i.e.DAO 2016-08 and DAO 2021-19)